

## Second Fix Checklist

### New Build + Renovation

Please use this as a guide for what needs to be in place before we attend site.

If the project includes having ASHP & Cylinder

- First fix plumbing (if not installed by Eco) to be complete (and labelled up)
- ASHP base built including drain/soakaway
- Floor of the plant room to be as complete as you would like it to be.
- Walls plasterboarded and as decorated as you would like it to be.
- No obstructions to the location of the ASHP e.g. scaffolding
- Final wall covering/cladding/rendering complete

If the project includes having UFH

- UFH installed, filled & tested.

If the project includes having radiators

- Radiator sizes confirmed – radiator schedule signed off by customer & Jack

If the project includes second fixing for plumbing

- Bathroom layouts confirmed – designs available or **exact** locations of sanitary ware marked on the walls/floor
- All tiling and grouting to be complete before we arrive on the first day.
- **All** sanitary ware, showers, shower trays, wastes and any items to be fixed into the wall e.g. taps/shower valves **must be on site** before we attend on the first day.

Any items that the customer is supplying for Eco Installer to install **MUST** be on site on the first day of the booking. (This includes towel warmers.)